

## Detailed Takeoff Report

Client Name: <>

Plan Name: <>

Delivery Address: <>

Delivery Address: <>

Item Description	UOM	Comments	Quantity
<b>Concrete Reinforcement</b>			
CMU Foundation Rebar (For Downcells)			
CMU Rebar - #5 x 4'-0" L-Bar	EA		39
<b>CMU Walls - 1st Floor</b>			
CMU Blocks			
CMU - 8 x 8 x 8 Half Block	EA		84
CMU - 8 x 8 x 16	EA		1849
CMU - 8 x 8 x 16 Open Bottom Bond Beam	EA		172
CMU - 12 x 8 x 12 Pilaster	EA		35
CMU Precast Lintels			
CMU Precast Lintel - 8" x 8" x 4' 6"	EA		6
CMU Precast Lintel - 8" x 8" x 4' 8"	EA		1
CMU Precast Lintel - 8" x 8" x 5' 10"	EA		1
CMU Precast Lintel - 8" x 8" x 7' 4"	EA		1
CMU Precast Lintel - 8" x 8" x 17' 4"	EA		1
CMU Precast Sills			
CMU Precast Window Sill - 3' 1"	EA		6
CMU Precast Swing Door Threshold - 3' 3 1/2"	EA		1
CMU Precast Sliding Glass Door Threshold - 6' 0"	EA		1
CMU Wall Rebar			
CMU Rebar - #5 x 20'	EA		38
CMU Joint Reinforcement			
CMU Ladder-Type Joint Reinforcement - 8" x 10'	EA		154
CMU Grout Screen			
CMU Mortar/Grout Screen - 8" x 100'	EA		3
CMU Block Mortar			
CMU Masonry Cement - Type S (80 lb. Bags)	Bags		76
CMU Masonry Sand	CU YD		11
CMU Block Core-Fill Masonry Grout			
CMU 2500 PSI Grout	CU YD		6
CMU Truss Anchors			
Simpson - Embedded Truss Anchor - META16	EA		122



## Detailed Takeoff Report

Stucco					
	Stucco				
		Stucco (Net Surface Area)	SF		1923