

Takeoff Summary Report

Client Name: <>

Plan Name: <>

Delivery Address: <>

Delivery Address: <>

Item Description	UOM	Quantity
Concrete		
CMU Rebar - #5 x 4'-0" L-Bar	EA	39
CMU Masonry		
Simpson - Embedded Truss Anchor - META16	EA	122
CMU - 8 x 8 x 8 Half Block	EA	84
CMU - 8 x 8 x 16	EA	1849
CMU - 8 x 8 x 16 Open Bottom Bond Beam	EA	172
CMU - 12 x 8 x 12 Pilaster	EA	35
CMU Precast Lintel - 8" x 8" x 4' 6"	EA	6
CMU Precast Lintel - 8" x 8" x 4' 8"	EA	1
CMU Precast Lintel - 8" x 8" x 5' 10"	EA	1
CMU Precast Lintel - 8" x 8" x 7' 4"	EA	1
CMU Precast Lintel - 8" x 8" x 17' 4"	EA	1
CMU Precast Window Sill - 3' 1"	EA	6
CMU Precast Swing Door Threshold - 3' 3 1/2"	EA	1
CMU Precast Sliding Glass Door Threshold - 6' 0"	EA	1
CMU Rebar - #5 x 20'	EA	38
CMU Ladder-Type Joint Reinforcement - 8" x 10'	EA	154
CMU Mortar/Grout Screen - 8" x 100'	EA	3
CMU Masonry Cement - Type S (80 lb. Bags)	Bags	76
CMU Masonry Sand	CU YD	11
CMU 2500 PSI Grout	CU YD	6

Takeoff Summary Report

Masonry Veneer

Stucco (Net Surface Area)

SF

1923